Project #: 191028

Start Date:
Completion Date: **Winter 2019**
Status: **Completed**

Pit Meadows - CP Rail Auto Compound

Contract Value: $946,789.33 Orignal Contract Value: $946,789.33



Project Highlights:

- 58,000 m2 of 100mm Gravel Base Placement (13,000 MT)
- 58,000 m2 of Fine Grading
- 8,000 MT of Asphalt Paving
- 1,460 m of Asphalt Extruded Curbing

Description:

This project was Graded and Paved in Echelon using the latest Top-Con 3DMC GPS System, a technology accurate to 1mm.

Team Members:

• Rod Stephens - Project Director
• Denis Labelle - Construction Manager
• Greg Regier - Estimating Manager
• Max Spedding - General Paving Superintendent

Client Information:

JJM Construction
Keith Prystay, Robbie Plavcic
T: 604-946-0978

Project Engineers:

R.F. Binnie & Associates Ltd.
T: 604-420-1721

